BANGALORE DIVISION.

FORM OF ADVERTISEMENT.

The 24th September 1904.

1. Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Bangalore Division, up to 5th October 1904, for restoring the Chickan Ane tank, Registered No. 168, Nelamangala Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1905.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Bangalore between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 100 (One hundred) in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for restoring Chickan Ane, Nelamangala Taluk," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Detailed abstract estimate of restoring Chickan Ane tank, Registered No. 168, Nelamangala Taluk:—

Items of work.	*Per.*	*Quantity.*
Bund—		
Earth-work	C. yd.	1,365
Turfing	Sq. yd.	2,201
Removing and repairing grade stones	No.	20
New grade stones	"	4
Index stones, new	"	24
Register number stones	"	1
Gauge stones	"	1
New stone work	C. yd.	202
Gravel backing to revetment	"	49
Left waste weir—		
Earth-work	C. yd.	5,337
Concrete in surki mortar	C. ft.	5,261
Brick in surki mortar	"	9,520
Burnt stone in surki mortar	"	6,322
Burnt stone slabs	Sq. ft.	3,317
Plastering with surki mortar	Sqr.	41·00
Pointing with do	"	57·92
Rough stone work, new	C. yd.	2,161
Dry stone filling (with old stones)	"	398
Blasting rock in front of weir	Lump sum.	

B. S. VENKATACHARIAR, *Executive Engineer.*

IN THE COURT OF THE MUNSIFF OF SERINGAPATAM.

Present: P. A. Sivaprakasam Pille, Esq., Munsiff.

Miscellaneous No. 169 *of* 1904-05.

In the matter of the estate of Singra Iyengar of Melkote, Seringapatam Taluk ... *Deceased.*

Srirangamma ... *Applicant.*

Whereas Srirangamma claiming to be the wife of the said Singra Iyengar, deceased, has applied for a certificate under Section 17 of Regulation No. VII of 1901, to collect debts to the